


Certificate No: 0604/2015

Supplier No:884



**Gambia
Public Procurement Authority**

Value for Money in Public Procurement
GAMBIA PUBLIC PROCUREMENT ACT 2001

**Certificate of Supplier / Contractor
Registration**

FAKORO JARRA CONSTRUCTION

Is registered with the Gambia Public Procurement Authority
For the year 2015,


Type of Business: **CONSTRUCTION ONLY**

This certificate is valid until the 31st day of December 2015,

Given under my hand this 23RD March, 2015.

ISSUING OFFICER

DIRECTOR GENERAL





THE GAMBIA

SRN: 0710367575

Form SWR3

Certificate of Business Registration

Is hereby granted to the under mentioned to carry on business in The Gambia

Name of owner of business **FAKORO JARRA**

Nationality of owner of business or in the case of company, country of Incorporation
THE GAMBIA

Name of Business **FAKORO JARRA CONSTRUCTION**

Type of Business **GENERAL CONSTRUCTION**

Place of Business **BASSE MANSAJANG KUNDA, FULLADU EAST, UPPER
RIVER, THE GAMBIA**

Residential address of owner of business or Registered Office (in the case of a Company)

Given under my hand
this 19th day of March 2015

Registrar of Companies



Fakoro Jarra
General Contractor
Basse Mansajang Kunda
Fulladu East, Upper River Region
Tel: 7070583

TO WHOM IT MAY CONCERN

Find attached the review and updated bill of quantity and cost,
for your perusal.

Sign: 

.....
Fakoro Jarra
General Contractor



St. Joseph's Lower Basic School					
NO.	DISCRIPTION	QUANTITY	UNIT	RATE GMD	AMOUNT
	Maisonry external and internal partitions cement sand block 2.0N/m2 cement sand mortar, sand block walls 150mm thick vertical	315	m2	300	94,500.00
	windows and doors DOORS				
	Steel encasement metal door glazed with 50x50 x2.5mm as frame complete iron mongery and union locks including prime and paint 2 finishe coats gloss paint to steel	5	Nr	3500	17,500.00
	WINDOWS				
	2 bags steel encasement window with glazing with fabricated bunglar bars	1	Nr	3000	3,000.00
	3 bays steel uncasement windows with glazing with fabricated bunglar bars	9	Nr	4000	36,000.00
	FINISHES				
	Render cement sand 1:4 mix) to new walls 12mm thick to walls	700	m2	125	87,500.00
	PAINTING				
	Painting to new walls prepare, price and paint 2 finish coast emulsion paint to render walls	700	M2	95	66,500.00
1	SUBSTRUCTURE				
	EXCAVATION				
A	Trenches and columns plts to receive foundation trenches 600x600x800depth	48	m3	120	5,760.00
B	Column plts 800x800x900	7	m3	120	840.00
C	DISPOSAL				
D	Excavated materials off site				
E	EXCAVATED MATERIALS				
	Filling to excavateions with materials arising from excavation trenches and plts				
F	Filling around building compacting	1	item	3500	3,500.00
G	Anti-termite treatment of foundation and filling with dursban or other	203	m3	50	10,150.00
2	PLAIN CONCRETE				
	Plain in-situ concrete lean mix 10N/mm2 10mm aggregate size wash aggregates			3000	3,000.00
	Sub-Total:				328,250.00

	CONCRETE WORK Reinforced insitu concrete 20N/mm ² 20mm aggregate size wash aggregate foundation				
A	Strip foundation	8	m3	4000	32,000.00
B	Column base 800x800x300 thick	3	m3	4000	12,000.00
C	Column 150x150mm	1	m3	4000	4,000.00
D	Floor slab 100mm thick	21	m3	4000	84,000.00
E	Extra over for trowel finish to unset concrete	1	m3	4000	4,000.00
	REINFORCEMENT HIGH YIELD STEEL BARS				
F	6mm starter bars	45	m	15	675.00
	12mm columns	80	m	35	2,800.00
	12mm bars columns bases	80	m	35	2,800.00
	FORM WORK				
G	To edges of slab	15	m2	100	1,500.00
	WALLS AND PARTITIONS MASONRY Cement sand block 2 on/mm ² cement mortar or equal approved cement sand block				
H	WALLS 150M THICK VERTICAL	82	M2	300	24,600.00
	SUPERSTRUCTURE				
A	Columns 150x150mm	1	m3	4000	4,000.00
B	Lintel 150x200mm	3	m3	4000	12,000.00
	REINFORCEMENT				
	Reinforcement high yield steel bars				
C	6mm to columns	110	m	15	1,650.00
D	12mm to columns	170	m	45	7,650.00
E	6mm to lintel at 200mm centre	250	m	15	3,750.00
F	12mm to lintels	400	m	35	14,000.00
	FORM WORKS				
G	Columns	15	m2	100	1,500.00
H	Lintels	80	m2	100	8,000.00
	Floor finishes to offices only unglazed porcelain tiles to floor area on 40mm semi-dry cement /sand screed	35	M2	450	15,750.00
	skirting tiles 100mm	34	M2	50	1,700.00
	CEILING 6mm ceiling plywood to 50x50mm treated ward wood timber joest at 600mm centres including woulding to offices	35	M2	500	17,500.00
	Sub-Total:				255,875.00

	PAINTING AND DECORATION prepare, prime and paint 2 finishes coats emulsion timber works windows and fascia boards	1	1 item	3000	3,000.00
A	ROOF fabricated mild steel roof 40x40x2mm with 4r 12dia 50x75mmx5mmx150mm long mild steel angle cleats welded to top chord of roof 90x130 x 5mm bearing plate camming 12mm dia.	13	No	3000	39,000.00
B	touch with red oxide after fixing apply 1 coat and one coat full gloss finish	13	Nr	250	3,250.00
C	50x50x5mm steel angle purlins 1000mm centres fixed to 50x50mm touchup with red oxide	300	M	200	60,000.00
D	200x25mm hard wood timber fascia board	72	M	150	10,800.00
E	Roof ridge	29	M	500	14,500.00
F	Aluzin profile (0.5mm) gauge single span roofing sheets	320	M2	400	128,000.00
Sub-total					258,550.00

Sub-Total: 1:	328,250.00
Sub-Total: 2:	255,875.00
Sub-Total: 3:	258,550.00
Grand Total:	842,675.00

FAKORO JARRA. TEL: 7070583
GENERAL CONTRACTOR
BASSE MANSAJANG
 DATE 23/3/2015
 SIGN